

ADDENDUM NO. 1

Date: January 23, 2019

Owner: Travis County MUD #4

Project Name: Travis County MUD #4 North Wastewater Treatment Plant Unit #1 Rehabilitation

This Addendum forms a part of the Contract Documents and clarifies, corrects or modifies original Bid Documents, dated February 2019. Acknowledge receipt of this addendum in space provided on bid form. Failure to do so may subject Bidder to disqualification.

The purpose of Addendum No. 1 is to amend the Contract Documents; no revision to Contract times is made.

A. Project Manual Revisions:

Measurement and Basis of Payment item number W-19, page 18, ADD "This items also includes the installation of two (2) 1.5" conduits buried in the same trench as the IPW piping. Stub-up locations shall be installed near the stairs to Unit #1, and near the existing panel rack for the filter units as shown in the plans. Conduits shall be installed with pull-tape. The approximate length of each conduit is 96 feet."

B. Drawing Revisions:

Attached.

This addendum consists of 2 pages and 1 sheets.



Approved by Engineer

End

Item No. W-19, Install Pipe for In Plant Water System, will be paid for at the unit contract price, per lump sum, complete and in place, which price shall be considered full compensation for furnishing all materials, equipment, tools, labor, submittals, overhead, and incidentals necessary to install all the required piping for the in plant water system. Included in this item are digging, backfill, cut through existing driveway, repave damaged sections of driveway, fittings, appurtenances, tie-ins, and any modifications required for the proper installation of approximately 25 feet of 4" class 250 ductile iron pipe, 135 feet of 3" SDR 21 PVC pipe, and 30 feet of 2" SDR 21 PVC pipe as shown on the drawings. Pipes must be purple and have black stenciling reading "NON-POTABLE WATER, DO NOT DRINK" and "NO BEBA AL AGUA". Included in this item is the installation of new pressure reducing valves as required and shown on the drawings and contract documents to lower the in plant water system pressure to acceptable levels for the hose bibs and future new head works system. This items also includes the installation of two (2) 1.5" conduits buried in the same trench as the IPW piping. Stub-up locations shall be installed near the stairs to Unit #1, and near the existing panel rack for the filter units as shown in the plans. Conduits shall be installed with pull-tape. The approximate length of each conduit is 96 feet.

